

JAYPEE INFRATECH LIMITED
Quoting Sheet for the Contractors

Name of Work		Re-surfacing on Structures & Approaches with Micro-Surfacing Type – III (Phase – II) at Yamuna Expressway Chainage – KM 95.00 to KM 165.00 from Mathura to Agra, Uttar Pradesh, India,		
S.No.	Item Description	UOM	Amount (INR)	Remarks
1	1) Providing and laying micro-surfacing type-III 6-8mm (six to eight millimetre) thick layer comprising of crushed aggregate of specific size conforming to Type-III grading @14 Kg per Sqm (Fourteen Kilogram per square metre) of road surface coverage. 2) Milling out the top bituminous undulated surface upto 20 MM only from distressed / ravelled areas removal and carriage of material by vehicle from the structure to a suitable dump site outside the expressway as per direction of engineer in-charge. Thickness & Area as per site requirement for surface levelled and suitable for Micro-surfacing work. 3) Repair of Jerks & depressions between Structures & Approaches, filling of depressions with cold mix material levelling and compacting with vibratory roller complete as per the direction of Engineer In-charge.	Sqm		
	Item Includes restore the surface with necessary repairs of potholes cracks ruts and undulations etc. prior to the micro surfacing work. Make the surface levelled & smoother with zero undulations for good to lay the layer of Micro-surfacing Type - III. The repair work shall be as per the MORTH & IRC guidelines or as per the direction of Engineer In-charge.			
TOTAL AMOUNT			-	

Rate per Square Meter of Micro-surfacing Work (in Words) -

Total BOQ Amount (in Words) -